G. R. S. 59

3PB—15,000—22-7-14

GENERAL AND REVENUE SECRETARIAT.

1900
~~191~~
(R B)

File No. 41 of 1900

Serial Nos. 1—2

~~Papers Filed.~~

Month March 1901

SUBJECT.

Construction of a well at Andenahalli village, Sadri Taluk

Addressed — [illegible]

PREVIOUS REFERENCES.	LATER REFERENCES.
3782 1899	

Commissioner
[illegible]

97

L 1645

~~97~~

Received 1901

10393 ~~189~~

16 Mar: 01

From The President of the Local Fund Board Kadur Circle

To The Secretary to the Government of Mysore General & Rev: Department

Dated 15th March 1901

Despatched

Received

General No. 555

No.

To the Chancery

No 12736/1898/3

Enclosure No. 3

Submitting a revised Estimate for Rs 793/- for constructing a Square well at Anderahalli village in the Kadur Taluk for favor of Government Sanction

SECTION L.B

FILE No. 91 of 1900

SER. No. 1

16.3.01

A. S. Chen

19/3/01

Draft put up

Mat

20/3

1900 - 1901

Kadur District Local Fund Board
President's Office
Dated Chikmagalore 15th March 19

From.

H. H. Parkes Esqre
President of the
Local Fund Board
Kadur Circle

To

The Secretary to the
Government of Mysore
General & Revenue Departments.

Sir.

I have the honor to submit herewith for favor of Government sanction a revised estimate for Rs 793/- for constructing a square well at Indenahalli village in the Kadur Taluk.

2 The original estimate sanctioned by the President in the month of March 1900 was for Rs 484/- and the depth of the well as per original estimate was 48 ft, which is also enclosed for favor of perusal.

3 The Assistant Commissioner in charge of the Northern division after inspecting the work reports that though the well has been sunk to a depth of 48 ft and water has just been tapped, the well will have to be deepened 10 ft more to ensure an unfailing supply of water for the use of the villagers. Hence the revised estimate.

The excess of Rs 309/- over the original estimate may be met out of Rs 5000/- sanctioned in G.O. No. 175 F-8 dated 3. 8. 1900. A copy of the abstract of the revised estimate is enclosed.

I have the honor to be,
Sir
Your most obedient Servant

The revised estimate for constructing a square well at Andenahalli village in the Kadur Taluk —

Abstract 7 — [illegible]

Items	Per	Rate	Quantity	Amount
Earth work Excavation	Cyd	a. 4	80	20
Blasting Rock from 30 ft up to 45 ft	Cyd	4 a	45	180 a
Do up to 60 ft	-Do-	6 a	31¼	187 a
Burnt Stone Slabs dressed	sqft	a. 6	350	131 a
Pulleys with iron works	no.	5 a	2	10 a
Burnt stone lining	Cyd	3 a	80	240 a
Packing Earth	-Do-	2	40	5 a
Levelling the ground and Bailing water &c	Ls.			20 a
Total value of the Estimate			Rs	793 a
Deduct amount already sanctioned			Rs	484 a
Net amount to be sanctioned by Government				309 a

Rupees three hundred and nine only

Chikmagalur
11th March 1901

[illegible]
Vice President of the

4 99 ~~101~~

Read

Letter no. 555 dated the 15th March 1901 from the President of the D. T. Board Kadur S. T. circle stating that an estimate for Rs 482/- ~~was sanct~~ for sinking a well at Andenahalli in the Kadur Taluk was sanct by the President and the well sunk to a depth of 40 ft the depth provided for in the estimate, and that although water has been tapped at that depth a further deepening of 10 ft is considered necessary to ensure an unfailing ~~supply~~ supply of water, and submitting a revised estimate for Rs 793/ for the same

L. B.
91 of 1900
2
SER

Order No. 12736-37 / L.7.15-99 of 29/3/01.

Encl: 2 to P. & one to Compt.

Pd. L. 1728

The revised estimate received with the above is sanctioned.

The extra cost of Rs 309/- after deducting the amount of original estimate with, as proposed, be met from the sum of Rs 5000/- sanctioned from the L.7. Pool in Govt. Prop:

vide L.B. 18 of 99 & 100 Sl. 7;

No. 1757-D / L7.15-99 of the 3rd Aug 1900

27/3/01

26/3/01

Under Secty.

Bnj 2 31/3/01

To

The Presd: O.7. B. Kaiser circle returning the sanctd estimate together with copy of abstract estimate